

2 100142

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 152 173-20236-00-00
NW WNW, SEC. 17, T 26 S, R 2 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3004

Operator: Gressel Oilfield Service
Name & Address Box 607
Burrton, KS 67020

_____ feet from S section line
_____ feet from E section line

Lease Name Galyart Well # 4
County Sedgwick 112.52

Well Total Depth 3462' PBD 3460 feet

~~EXXEXX~~ Pipe: Size 4 1/2 feet 3462-150 sks.

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated perf 3336-3340'

Plugging Contractor Gressel Oilfield Service License Number 3004

Address Box 607, Burrton, KS 67020

Company to plug at: Hour: 3:00 Day: 8 Month: 8 Year: 19 86

Plugging proposal received from Ed Gressel

(company name) Gressel Oilfield Service (phone) _____

were: sand to 50' above perfs - dump bail 4 sacks of cement on bottom,
pull recoverable casing - bail fluid to 60' below surface -build bridge and
dump redi-mix to ground level

Plugging Proposal Received by District Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00 Day: 8 Month: 8 Year: 19 86

ACTUAL PLUGGING REPORT Sanded back to 2900 feet and dumped 4 sacks of cement. Bridge: at
2950 feet - for bottom. BUilt rock bridge at 275 feet. Bailed fulid down 20' to
250 feet. Dumped redimix to surface.

Remarks: Rudd & Son Redi-Mix Haysville #88985 3 yards
(if additional description is necessary, use BACK of this form.)

INVOICED
(did not observe this plugging.)
AUG 15 1986

DATE _____

8-14-86 Signed J. C. Sanders
W AUG 14 1986 (TECHNICIAN)

INV. NO. 14733 SEP 10 1986