

2 030849

9-6

KHLP
AP

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20, ~~22816000~~
C N/2 NE, SEC. 22, T 26 S, R 2 W/E

4620' feet from S section line
1320' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107

Lease Name Lygrisse Well # 22-1

Operator: H-30, Inc.

County Sedgwick 107.87

Name & Address 251 N. Water, #10

Well Total Depth 3319' feet

Wichita, KS 67202

~~Casing~~ Pipe: Size 5-1/2" feet 3300'/100 SX

Surface Casing: Size 8-5/8 feet 250' CTS

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Dale Wilson (W. W. Drilling) License Number 6012

Address RR #3, ElDorado, KS 67042

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Dale Wilson

(company name) W. W. Drlg (phone) 316-321-1167

work: Gravel hole to 3250' - dump 6 sx cement - rip and pull casing - set rock
bridge 300' - dump slurry mix to surface.

RECEIVED
STATE CORPORATION COMMISSION
9-15-89
SEP 15 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 15:00 Day: 6 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT Gravel hole to 3250' - dumped 6 sx cement/bailer - ripped
and pulled 2423' of 5-1/2" casing - set rock bridge 300' to 280' - Lewis &
West #14872 dumped 5 yds slurry mix 10% sand to surface.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-21-89

Signed Don Thompson
(TECHNICIAN)

INV. NO. 25916
9-6