

2 030745

11-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,822-00-00

S/2 SE NW, SEC. 22, T 26 S, R 2 WXE

2970 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107

Lease Name Jeffries Well # 4

Operator: H-30 Drilling, Inc.

County Sedgwick 108.36

Name & Address 251 N. Water, #10

Well Total Depth 3334' Simpson feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8" feet 207'/160 sx

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor H-30 Drilling Inc. License Number 5107

Address Wichita, KS 67202

Company to plug at: Hour: 08:00 Day: 24 Month: 11 Year: 19 88

Plugging proposal received from Gene McAllister

(company name) H-30 Drilling, Inc. (phone) 316-263-2043

were: Fill hole with mud - run drill pipe 1150' - spot 35 sx cement - pull drill pipe to 270' - spot 35 sx cement - pull dp to 60' - spot 25 sx cement - run 1 joint dp in rat hole - cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
12-8-88
DEC 8 1988

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 Day: 25 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT Filled hole/mud - ran drill pipe to 1150' - United Cementing #3052 spotted 35 sx 60/40 pozmix 2% gel - pulled drill pipe to 270' - spotted 35 sx 60/40 pozmix 2% gel - pulled drill pipe to 60' - pumped 25 sx 60/40 pos 2% gel to surface - ran 1 joint drill pipe in rat hole - pumped 10 sx cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

I did not observe this plugging.

DATE 23291

INV. NO. 23291

Signed Don Thompson (TECHNICIAN)