

9-15

2-080059

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-173-20,617-00-00

NE SE NW, SECTION 22 TOWNSHIP 26 RANGE 2E

OPERATOR LICENSE # 30437
OPERATOR UNITED CEMENTING & ACID CO INC
NAME & P.O. BOX 712
ADDRESS EL DORADO, KS 67042

3630 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE
LEASE NAME: JEFFERIES #2
COUNTY: SEDGWICK
WELL TOTAL DEPTH: 3204' 104.13
PIPE: 5 1/2" @ 3202'
SURFACE CASING: 8 5/8" @ 209'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: QUALITY WELL SERVICE

ADDRESS: 249 EAST BETH, STERLING, KS LICENSE: 31925

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RICHARD McINTYRE

COMPANY NAME: QUALITY WELL SERVICE PHONE:

WERE: SAND BACK 50' ABOVE PERFORATION. CAP WITH CEMENT. SHOOT OFF AT 300',
CIRCULATE CEMENT TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 12:50PM DAY: 15 MONTH: 9 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BACK TO 2717'. CAPPED THRU BAILER WITH 5 SACKS OF
CEMENT. WELL HAD BEEN SQUEEZED FROM 1200'- 30'. NO PIPE RECOVERY. RAN 1"
TUBING TO 273' AND CIRCULATED CEMENT. RAN TUBING TO 23', CIRCULATED CEMENT
TO SURFACE ON BACKSIDE.

REMARKS:

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 28 1997
10-28-97
CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

Doug Louis
DOUG LOUIS

INVOICED
DATE OCT 29 1997
INV. NO. 49383