

2 030756

1-4

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,658-00-60

SE NE NW, SEC. 22, T 26 S, R 2 xW/E

4290 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 05107

Lease Name Jefferies Well # 3-A

Operator: H-30 Inc.

County Sedgwick 109.36

Name & Address 251 N. Water, #10

Well Total Depth 3365' PBSD 3351' feet

Wichita, KS 67202

Conductor Pipe: Size 4-1/2" feet 3352'/165' sx

Surface Casing: Size 8-5/8" feet 221'/95' sx

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor W. W. Drllg. Co. License Number 6012

Address RR #3, Box 66, El Dorado, KS 67042

Company to plug at: Hour: Day: 3 Month: 1 Year: 19 89

Plugging proposal received from Dale Wilson

(company name) W. W. Drilling (phone) 316-321-1167

were: Run tub to perforations - spot 25 sx cement - shoot & pull casing - set
rock bridge 270' - dump redi mix to surface

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

JAN 26 1989
1-26-89

CONSERVATION DIVISION
Wichita, Kansas

Perf 3206' Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 13:30 Day: 4 Month: 1 Year: 1989

ACTUAL PLUGGING REPORT Ran 2" tub to 2600' - tub stopped - Halliburton Services #745432

spotted 30 sx cement - pulled tub to 1550' - spotted 30 sx cement - pulled tub -
pulled 1233' of 4-1/2" csg - set rock bridge 300' to 280' - hole dry - Lewis &
West #13010 dumped 5-1/2 yds slurry mix 10% sand to surface.

Remarks: In additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-27-89
INV. NO. 23787

WC

Signed Don Thompson (TECHNICIAN)