15-141-20072-00-00

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above Section Plat

WELL PLUGGING RECORD

Osborne County. Sec. 10 Twp. 9S Rge. 15W E/W
Location as "NE/CNW¼SW¼" or footage from lines
C SW 1/4 SE 1/4
Lease Owner Graham-Michaelis Corporation
Lease Name Beisner Well No. #2-10
Office Address P.O. Box 247 Wichita, Kansas 67201
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed 9-7 1980
Application for plugging filed 9-7 1980
Application for plugging approved 9-7 1980
Plugging commenced 9-7 11:00 P.M. 1980
Plugging completed 9-8 5:15 A.M. 1980
Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production
19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation Depth to top Bottom Total Depth of Well 3776'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

8 5/8 277"
CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|---|---|---|---|---|---|---|
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole 660' with heavy mud; mixed 60 sacks cement and pumped in hole thru drill pipe.

Filled hole to 270' with heavy mud; mixed 30 sacks cement and pumped in hole thru drill pipe.

Filled hole to 40' with heavy mud; built dbridge with hulls; mixed 10 sacks cement and filled hole to bottom of cellar; mixed 5 sacks of cement and poured in rat hole.

All cement used was 50-50% Poz Mix 4% gel.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Revlin Drlg., Inc.

STATE OF Kansas COUNTY OF Russell, ss.
Stanley C. Lingreen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Stanley C. Lingreen
P.O. Box 293 Russell, Kansas 67665
(Address)

LOIS E. DAVIS
Russell County, Ks.
My Appt. Exp.

SUBSCRIBED AND SWORN TO before me this 10th day of September, 1980

Lois E. Davis
Notary Public.

My commission expires July 9, 1983

9-11-80