

15-141-20099-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Osborne County, Sec. 10 Twp. 9S Rge. 15W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C NE NE SW

Lease Owner Graham-Michaelis Corporation  
Lease Name Finnessy Well No. 1-10  
Office Address 211 N. Broadway, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed June 10 1981  
Application for plugging filed June 10 1981  
Application for plugging approved June 10 1981  
Plugging commenced June 10 1981  
Plugging completed June 10 1981

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3700'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug at 780' with 50 sacks.  
2nd plug at 300' with 30 sacks.  
3rd plug at 40' with 5 sacks.

Plug was down at 10:00 a.m. 6/10/81.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 1981


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Abercrombie Drilling, Inc. 6-22-81  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Vice President (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1981

My commission expires 2-14-85  
Suzanne M. Hofer  
Suzanne Hofer Notary Public.



CONTRACTOR'S WELL LOG

15-141-20099-00-00

OPERATOR:  
CONTRACTOR:  
WELL NAME:  
LOCATION:

Graham-Michaelis Corp.  
Abercrombie Drilling, Inc.  
FINNESY #1-10  
C NE NE SW, Section 10-9S-15W  
Osborne County, Kansas

SPUD DATE:  
COMPLETION DATE:

6-03-81  
6-10-81

0	150	Clay & Sand
50	279	Sand & Shale
279	420	Shale
420	1247	Shale & Sand
1247	1283	Anhydrite
1283	1780	Shale
1780	2205	Shale & Lime
2205	2299	Lime & Shale
2299	2535	Shale & Lime
2535	2770	Lime & Shale
2770	2985	Shale & Lime
2985	3168	Lime & Shale
3168	3598	Lime
3598	3700	Lime & Conglomerate
	3700	Rotary Total Depth

Spud hole at 2:45 p.m., 6/03/81. Cut 279' of a 12 1/2" hole. Ran 6 Joints of 8 5/8" - 24# casing. Set at 277.15', cemented with 225 sacks of common 2% Gel, 3% Ca. Cl. Cement did circulate. Plug down at 7:25 p.m., 6/03/81. Drilled plug at 5:30 a.m., 6/04/81. 7:00 a.m. drilling @ 420'. Bit #1 y-11 (SN 913006).

RTD @ 3700'. Set 1st plug @ 780' with 50 sacks. Set 2nd plug @ 300' with 30 sacks, Set 3rd plug @ 40' Solid Bridge, 5 sacks in rathole, 50-50 posmix, 4% Gel, 3% C.C. Job complete at 10:00 a.m. 6/10/81.

SAMPLE TOPS:

Anhydrite 1247'  
B/Anhydrite 1283'

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 1981

STATE OF KANSAS

COUNTY OF SEDGWICK

CONSERVATION DIVISION  
Wichita, Kansas

6-22-81

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the FINNESY #1-10, C NE NE SW, Section 10-9S-15W, Osborne County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 16th day of June, 1981.

Suzanne M. Hofer  
Suzanne Hofer

