

15-141-20110-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Osborne SEC. 10 TWP. 9S RGE. 15W E/W  
 Location as in quarters or footage from lines:  
C W/2 NE SE

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Lease Owner Graham-Michaelis Corporation  
 Lease Name Beisner Well No. 3-10  
 Office Address Box 247 Wichita, Kansas 67201  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed 8-18-81  
 Application for plugging filed 8-18-81  
 Plugging commenced 8-18-81 1:00 AM  
 Plugging completed 8-18-81 3:00 AM  
 Reason for abandonment of well or producing formation Dry Hole

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|------|--------|------------|
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |
|           |         |      |    |      |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Filled hole to 740' with heavy mud and mixed 60 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 300' with heavy mud and mixed 40 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 40' built bridge pushed down plug and mixed 10 sacks of cement and filled hole to bottom of cellar; mixed 5 sacks and poured into the rat-hole.

All cement used was 50-50 Poz Mix 6% Gel 3% CC

RECEIVED

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Revlin Drlg., Inc.

AUG 19 1981

CONSERVATION DIVISION

Wichita, Kansas

STATE OF Kansas COUNTY OF Russell, ss.

Stanley C. Lingreen (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

8-19-81



(Signature) Stanley C. Lingreen  
Box 293 Russell, Kansas 67665  
 (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 81

Paula J. Gibson  
 Notary Public.

My Commission expires: November 10, 1984