

15-41-00040-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Osborne County. Sec. 12 Twp. 9 Rge. 15 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner Trans Era Petroleum, Inc.

Lease Name Beck Well No. #1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5/26/55 19

Application for plugging filed 5/25/55 19

Application for plugging approved 5/25/55 19

Plugging commenced 5/26/55 19

Plugging completed 5/26/55 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt

Producing formation Depth to top Bottom Total Depth of Well 4010 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	193	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

WELL PLUGGING RECORD

Layed down drill pipe. Set first plug at 225'. Filled hole to 225' with heavy mud, ~~20~~ using 20 sacks cement and 1/3 sack hulls. Set second plug at 35'. Filled with heavy mud, using 10 sacks and 1/3 sack hulls. tied top plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

Robert B. Snyder (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert B. Snyder

(Address)


SUBSCRIBED AND SWORN TO before me this 20 day of June, 19 55

Margie Cooper

Notary Public  
STATE CORPORATION COMMISSION

6-22-55

CONSERVATION DIVISION  
Wichita, Kansas



PLUGGING  
FILE SEC 12 T 9 R 15 E  
BOOK PAGE 23 LINE 7

15-141-00040-00-00

Trans Era Petroleum, Inc.  
Beck #1

NW NW SE 12-9-15  
Osborne County, Kansas

Comm: 5/13/55  
Comp: 5/26/55

Total Depth: 4010

Casing and Cement

8 5/8" @ 193# with 150 sacks of Lone Star

FORMATION	DEPTH
Shale, Sand & Shale	875
Shale & Sand	1080
Red Bed	1190
Anhydrite	1240
Shale, Sand & Shale	1475
Shale	1694
Shale & Lime	3215
Lime	3500
Lime & shale	3595
Lime, Shale & Chert	3690
Cherty Lime	3820
Lime	3870
Cherty Lime	3900
Lime & Shale	3965
Arbuckle	4010

STATE OF KANSAS )  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

*Robert B. Snyder*

Subscribed and sworn to before me this 20th day of June, 1955.

*Margie Cooper*  
Notary Public



My commission expires 1-30-57

**PLUGGING**  
FILE SEC 12 T 9 R 45E  
BOOK PAGE 23 LINE 7

STATE OF KANSAS  
6-22-55  
CONSERVATION DIVISION  
Minnie Cooper