

15-141-20082-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Osborne County. Sec. 15 Twp. 9 Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NW SE

Lease Owner Shields Oil Producers, Inc.
Lease Name Finnesy "A" Well No. 1
Office Address Shields Bldg., Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed 12-8 19 80
Application for plugging filed " 19 80
Application for plugging approved " 19 80
Plugging commenced " 19 80
Plugging completed " 19 80
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plot

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation Depth to top Bottom Total Depth of Well 3,785'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	247'	Cmtd W/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

- Fill hole w/heavy mud
- Push bridge plug to 720'
- Dump 60 sax cement on plug thru 4 1/2" drill pipe
- Push bridge plug to 240'
- Dump 30 sax cement on plug thru 4 1/2" drill pipe
- Push bridge plug to 40' w/ 1/2 sax hulls on plug
- Dump 10 sax cement on plug to celler
- Dump 5 sax cement in rat hole and mouse hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.

STATE RECEIVED
CORPORATION COMMISSION
DEC 12 1980
CONSERVATION DIVISION
Wichita, Kansas
12-12-80

STATE OF Kansas COUNTY OF Russell
R. L. Shields (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R L Shields
Shields Bldg., Russell, Kansas 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 11 th day of December, 19 80

Ruth Phillips
Notary Public.

My commission expires

RUTH PHILLIPS
STATE NOTARY PUBLIC
RUSSELL COUNTY, KS.
My Appt. Exp. 5-26-83



Shields


15-141-20082-00-00

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers, Inc.
 Well: Finnesy "A" #1
 Commenced: December 1, 1980
 Completed: December 9, 1980
 Contractor: Shields Drilling Co., Inc.

Well Description: NW NW SE
 Sec. 15-9S-15W
 Osborne Co., Kansas



Elevation: 2,049' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	247'	Cmtd w/ 160 sax

..... Figures Indicate Bottom of Formations

Surface soil, clay & shale	253'
Shale & shells	500'
Shale & sand	1,274'
Anhydrite	1,313'
Shale	1,800'
Shale & lime	3,010'
Lime	3,785' RTD

RECEIVED
 STATE OF KANSAS
 CONSERVATION COMMISSION
 DEC 12 1980
 CONSERVATION DIVISION
 Wichita, Kansas

12-12-80

Notes