

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

15-141-20178-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Osborne SEC. 16 TWP. 9S RGE. 15 E/W  
 Location as in quarters or footage from lines:  
 NW SW SE


Lease Owner Woodman & Iannitti Drilling Company  
 Lease Name Pfortmiller Well No. 1  
 Office Address 1022 Union Center, Wichita, Kansas 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed September 24, 1983  
 Application for plugging filed September 24, 1983  
 Plugging commenced September 24, 1983  
 Plugging completed September 24, 1983  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

20 sx. @ 1275'  
80 sx. @ 845'  
40 sx. @ 300'  
10 sx. @ 40'  
10 sx. in Rathole  
Plugged with 50/50 Pozmix, 4% Gel, 3% CC

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 3 1983  
 CONSERVATION DIVISION  
 Wichita, Kansas

10-3-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing


STATE OF Kansas COUNTY OF Sedgwick, ss.  
K. T. Woodman (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman  
1022 Union Center, Wichita, KS 67202  
 (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 83

Kathryn A. Voigt  
 Notary Public.

My Commission expires: April 20, 1985 Kathryn A. Voigt



K. T. WOODMAN  
RES. PHONE 733-0418  
OFF. PHONE 265-7650  
WICHITA, KANSAS

D. J. IANNITTI  
PHONE 792-2921  
GREAT BEND, KANSAS

## WOODMAN & IANNITTI DRILLING COMPANY

*Rotary Drilling Contractors*

1022 UNION CENTER  
150 N. MAIN  
WICHITA, KANSAS 67202

15-141-20178-00-00

September 29, 1983

Company: Woodman & Iannitti Drilling Company  
Farm: Pfortmiller #1  
Location: NW SW SE  
Section: 16-9S-15W  
County: Osborne  
Contractor: Woodman & Iannitti Drilling Company  
Total Depth: 3430'  
Comm: September 20, 1983  
Comp: September 24, 1983  
Casing: 8-5/8" 24# set @ 255' w/180 sx. Common,  
3% CC, 2% Gel

Figures Indicate Bottom Formations:

255	Shale & Sand
400	Sand & Clay
1272	Shale
1280	Anhydrite
1304	Anhydrite
1800	Red Bed & Shale
1843	Lime & Shale
2170	Shale & Lime
2470	Lime & Shale
2650	Lime & Shale
2850	Lime & Shale
3050	Lime
3193	Lime & Shale
3315	Lime
3330	Lansing
3380	Lime
3430	Lime

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

*K. T. Woodman*  
K.T. Woodman, Partner

RECEIVED  
STATE CORPORATION COMMISSION

OCT 3 1983

CONSERVATION DIVISION  
Wichita, Kansas

103-83