

15-141-20033-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Osborne County, Sec. 18 Twp. 9 Rge. 15 ~~SE~~W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SE SW

Lease Owner A. Scott Ritchie
Lease Name Norris Well No. 1
Office Address Suite 950 - 125 N. Market, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed 10-10 19 77
Application for plugging filed 10-10 19 77
Application for plugging approved 10-10 19 77
Plugging commenced 10-10 19 77
Plugging completed 10-10 19 77
Reason for abandonment of well or producing formation _____

Dry Hole
If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3510
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		0'	219'	8 5/8"	219'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 1st plug was set @ 600' w/50 sacks cement
- 2nd plug was set @ 210' w/20 sacks cement
- 3rd plug was set @ 40' w/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet) 10-14-77

Name of Plugging Contractor Dreiling Oil, Inc.

STATE OF KANSAS COUNTY OF ELLIS, ss.
I, Joseph A. Hess, Sec. Treas. of Drlg. Contrc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph A. Hess

JOSEPH A. HESS
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 77

Cecilia Basgall
Cecilia Basgall Notary Public.

My commission expires November 17, 1980.

CECILIA BASGALL
NOTARY PUBLIC
Ellis County, Kansas

DREILING OIL, INC.

Victoria, Kansas 67671

15-141-20033-00-00

A. Scott Ritchie
Suite 950 - 125 N. Market
Wichita, KS 67202

WELL LOG

Company

Sec. 18

Twp. 9

Rng. 15

Farm

Norris

No. 1

Location

SE SE SW

Total Depth

3,510'

County

Osborne

Comm.

10-4-77

Comp. 10-10-77

Elevation:

2018

K. B.

Contractor

Dreiling Oil, Inc.

2015

D. F.

Rt. #1

Victoria, KS 67671

2013

G. R.

Casing Record

219' - 8 5/8"

Cement Record

135 Sacks cement

Production:

D & A

Figures Indicate Bottom of Formations


0'	43'	Post Rock
43'	224'	Shale
224'	975'	Shale & Sand
975'	1220'	Shale
1220'	1261'	Anhydrite
1261'	1400'	Shale
1400'	2997'	Shale & Lime
2997'	3510'	Lime
3510'	T.D.	

STATE OF KANSAS)

)ss

COUNTY OF ELLIS)

I, Joseph A. Hess, Secretary Treasurer of Dreiling Oil, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Norris #1.


Joseph A. Hess

Subscribed and sworn to before me this 13th day of October, 1977.


Cecilia Basgall Notary Public

My appointment expires: November 17, 1980.

CECILIA BASGALL
NOTARY PUBLIC
Ellis County, Kansas