

15-141-20023-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Osborne County, Sec. 26 Twp. 20S Rge. 15 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C SE SE  
Lease Owner Cities Service Oil Company

Lease Name Brown "C" Well No. 1

Office Address 209 E. William, 700 Sutton Pl. Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 2-7 19 74

Plugging completed 2-7 19 74

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Depth to top Bottom Total Depth of Well 3895 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 238    | None       |
|           |         |      |    | 5 1/2 | 3557   | None       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Howco squeezed or plugged well with 20 sacks. Common cement 15 sacks mud, released 5 1/2" plug and pumped 50 sacks common cement at 450 psi. Shut in pressure 150 psi.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 13 1974

CONSERVATION DIVISION  
Wichita, Kansas

02-13-1974

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

Address Hays, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

E. W. Peterman

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. W. Peterman

209 E. William, 700 Sutton Pl. Bldg. Wichita, KS 67202

DEAN CALDWELL  
State Notary Public  
Sedgwick County, Kansas  
Comm. Expires Oct. 16, 1977

Subscribed and sworn to before me this 11th day of February, 1974

Dean Caldwell

Notary Public.

My commission expires 10-16-77

15-141-20023-00-00

DRILLERS LOG

No. 1 Brown "C"

CASING RECORD:

8-5/8" @ 238'  
w/175 sx cement

5-1/2" @ 1261.71'  
w/500 sx cement

TOTAL DEPTH: 3,895'

COMPANY: Cities Service Oil Co.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: September 14, 1973

COMPLETED: September 30, 1973

DESCRIPTION:

C SE SE  
26-9S-15W  
Osborne County,  
Kansas

ELEVATION:

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|------------------|-------------|-----------|----------------|
| Shale            | 0           | 550       |                |
| Sand             | 550         | 590       |                |
| Shale            | 590         | 800       |                |
| Sand             | 800         | 915       |                |
| Redbed & Shale   | 915         | 1204      |                |
| Anhydrite        | 1204        | 1243      |                |
| Shale            | 1243        | 1900      |                |
| Shale & Lime     | 1900        | 2125      |                |
| Shale            | 2125        | 2130      |                |
| Shale & Lime     | 2130        | 2820      |                |
| Lime             | 2820        | 3613      |                |
| Lime & Chert     | 3613        | 3677      |                |
| Lime             | 3677        | 3770      |                |
| Lime & Chert     | 3770        | 3835      |                |
| Lime             | 3835        | 3895      |                |

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 5 1973  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jimmie L. Ferrice  
Jimmie L. Ferrice

Subscribed and sworn to before me this 11th day of October, 1973.

Linda W. Dickens  
Notary Public

My Commission Expires:

March 8, 1977

