

15-163-02828-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER n/a

LEASE NAME Beardmore

WELL NUMBER 11

SPOT LOCATION 660' fsl & 20' fwl

SEC. 2 TWP. 9 SRGE. 16 (X) or (W)

COUNTY Rooks

Date Well Completed 8/13/64

Plugging Commenced 6/7/85

Plugging Completed 6/7/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 North Water, Suite 300; Wichita, Kansas 67202

PHONE # (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Input  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays; District #6

Is ACO-1 filed? No If not, is well log attached? No

Producing formation LKC Depth to top 3122 bottom 3233 T.D. 3385

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1278'	----
				5 1/2"	3384'	210'
				4 1/2" KCC 2AP		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Hooked up to 8 5/8" casing and pumped 550 sacks 60/40 Pozmix w/10% gel, 3% CC; mixed 4 sacks hulls in last 450 sacks cement. ISIP - 100#. The annular volume between the 4 1/2" and 8 5/8" is 316 ft<sup>3</sup>. The volume of the 4 1/2" casing is 303 ft<sup>3</sup>. This totals 619 ft<sup>3</sup>. The 550 sacks of cement is equivalent to 957 ft<sup>3</sup>.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Murfin Drilling Company License No. 6033

Address 250 North Water, Suite 300; Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Pat Canaday, Hill City District, Jr. Engineer (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) P.O. Box 130, Hill City, KS. 67642



RECEIVED  
STATE CORPORATION COMMISSION  
SUBSCRIBED AND SWORN TO before me this 19 day of July, 1985

Donna Gerstner  
Notary Public  
Wichita, Kansas

My Commission expires: 6/24/89