

15-181-20010-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Sherman County, Sec. 12 Twp. 8S Rge. 40W (E) (W)  
C NW SE

Location as "NE/CNW&SW" or footage from lines \_\_\_\_\_  
Lease Owner Mack Oil Company  
Lease Name Hevner Well No. 1  
Office Address McCasland Shopping Center Box 400, Duncan, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) D&A  
Date well completed September 4, 1971  
Application for plugging filed September 4, 1971  
Application for plugging approved September 4, 1971  
Plugging commenced September 4, 1971  
Plugging completed September 4, 1971  
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5240 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	386'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud,  
set plug @ 2250' cemented  
w/100 sx 50-50 poz. set plug  
@ 400' cemented w/25 sx  
set plug @40' w/10 sx  
2 sx in rathole.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
09-16-1971

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Red Tiger Drilling Co.  
Address 1720 Wichita Plaza, Wichita Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Jim Farrice (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well is filed and that the same are true and correct. So help me God.

(Signature) Jim Farrice  
1720 Wichita Plaza, Wichita, Kansas  
(Address)

Subscribed and Sworn to before me this 7th day of September, 1971



Virginia B. Albert  
Notary Public.

My commission expires July 23, 1974

15-181-2000-00-00

DRILLERS LOG

No. 1 Hevner

CASING RECORD:	COMPANY:	Mac Oil Company	DESCRIPTION:
8 5/8" @ 386'	CONTRACTOR:	Red Tiger Drilling Company	C NW SE
w/225 ex cement	COMMENCED:	August 21, 1971	12-83-40W
	COMPLETED:	September 4, 1971	Sherman County, Kansas

TOTAL DEPTH: 5240'

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod	0	90	
Sand	90	290	
Shale	290	387	
Blue & Gray shale	387	1390	
Shale	1390	2525	
Shale and lime	2525	3170	
Anhy.	3170	3203	
Red bad, shale	3203	3225	
Shale & red shale	3225	3375	
Red shale	3375	3495	
Shale & limo	3495	3860	
Shale	3860	3920	
Shale & lime	3920	4140	
Lime	4140	5055	
Lime & shale	5055	5130	
Lime	5130	5240	

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 14 1971  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice  
Jim Farrice

Subscribed and sworn to before me this 7th day of September, 1971.



Virginia K. Albert  
Notary Public

My Commission Expires: July 23, 1974