

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-141-20,3220000

LEASE NAME Sigle Trust "A"

WELL NUMBER 1

2,310 Ft. from S Section Line

3,340 Ft. from E Section Line

SEC. 35 TWP. 9 RGE. 12 (E) or (W)

COUNTY Osborne

Date Well Completed 7-23-96

Plugging Commenced 7-23-96

Plugging Completed 7-23-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Russell Oil, Inc.

ADDRESS PO Box 272, Russell, KS. 67665

PHONE#(913) 483-3954 OPERATORS LICENSE NO. 3,293

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-23-96 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,440'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|-----------------|
| | | | | 8 5/8" | 207' | Cmtd. w/140 sax |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Push bridge plug to 920', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 765', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 250', pump 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS. 67665 KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Russell Oil, Inc. AUG 02 1996

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas.

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) SHIELDS BLDG., RUSSELL, KS. 67665

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 96

My Commission Expires:



Ruth Phillips
 Notary Public



Shields


Russell, Kansas

WELL LOG

15-141-20322-0000

Operator: Russell Oil, Inc.
 Well: Sigle Trust "A" #1
 Commenced: July 16, 1996
 Completed: July 23, 1996
 Contractor: Shields Drilling Co.

Well Description: N/2 NE/4 SW/4
 Sec. 35-9S-12W
 Osborne Co., Kansas



Elevation: 1,870' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

| Size | Run | Pulled |
|--------|------|-----------------|
| 8 5/8" | 207' | Cmtd. w/140 sax |

..... Figures Indicate Bottom of Formations

| | |
|--------------|------------|
| Shale | 210' |
| Shale & sand | 610' |
| Shale | 919' |
| Anhydrite | 951' |
| Shale | 2,885' |
| Shale & lime | 3,115' |
| Lime | 3,258' |
| Lime & shale | 3,400' |
| Lime | 3,440' RTD |

RECEIVED
 KANSAS CORPORATION COMMISSION

AUG 02 1996

CONSERVATION DIVISION
 WICHITA, KS