

15-141-30008-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Osborne County, Sec 3 Twp. 9 Rge 13W (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW 1/4 NW 1/4

Lease Owner Northern Ordnance Inc.

Lease Name Eva Vandament Well No. 1

Office Address Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 5-19-43 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 5-21-43 19

Plugging completed 5-21-43 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation None Depth to top Bottom Total Depth of Well 4125 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
None				10 3/4"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud 4123 to 265'
 Cement 265 to 235' 15 sax
 Mud 235 to 26'
 Cement 26 to 6'
 Soil 6 to Surface

PLUGGING
 FILE SEC 3-1-9-R13W
 BOOK PAGE 75 LINE 24



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to E. A. Rose
Address Box 786 Great Bend, Kansas

STATE OF _____, COUNTY OF _____, ss. _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. L. Pratt

(Address) Tulsa Oklahoma

SUBSCRIBED AND SWORN to before me this 19 day of June, 19 43

My commission expires May 4, 1947

My commission expires

Notary Public. Eleta Walker

My commission expires May 4, 1947 6929



+			
		3	

WELL RECORD:

WELL NO. 1 - 0 IN DEPTH, TOWNSHIP 9 NORTH, RANGE 13 WEST, OSBORN COUNTY, KANSAS

WELL NO. 1 - 0 IN DEPTH Section 8-34-13W, Osborne, (County, Kansas)

OPERATOR - HENRY HENRY CO. INC., Tulsa, Okla.

WELL NO. 1 COMPLETED - April 20, 1948

WELL NO. 1 COMPLETED - May 20, 1948

DEPTH - 0' to 4124'


Section 8, Township 9 North,
Range 13 West, (Osborne County, Kansas)

WELL LOG:

Set and cemented 14 jts. of 10-3/4" surface casing at 200' with 200 spikes Halliburton bulk cement.

WELL LOG:

FORMATION	FEET	DEPTH	FORMATION	FEET	DEPTH
Shale & Shells	0	40	Shale	3090	3057
Shale & Sand	40	135	Charly Lime	3057	3061
Shale & Shells	135	330	Lime	3061	3300
Red Sand & Shells			Lime (Shale)	3300	3363
Strata of Iron Pyrite	330	330	Lime	3363	3415
Red Sand & Shale	330	350	Shale & Lime	3415	3461
Lime	350	1070	Shale	3461	3485
Shale & Shells	1000	1230	Sand & Shale	3485	3490
Shale & Pyrite	1230	1340	Shale	3490	3501
Sand & Shale	1340	1400	Lime & Shale	3501	3525
Shale & Shells	1400	1630	Shale	3525	3538
Broken Lime	1630	1735	Sandy Shale	3538	3580
Lime	1735	1827	Shale	3580	3580
Broken Lime	1827	1912	Lime & Shale	3580	3610
Lime	1912	2057	Shale	3610	3627
Broken Lime & Shale	2057	2135	Charly Lime	3627	3633
Lime & Shale	2135	2233	Shert	3633	3700
Broken Lime & Shale	2233	2477	Shale	3700	3712
Lime & Shale	2477	2553	Lime & Shale	3712	3774
Sand & Shale	2553	2603	Lime (hard)	3774	3871
Lime & Shale	2603	2633	Lime	3871	3850
Shale	2633	2723	Lime & Shale	3850	4023
Lime	2723	2753	Shale	4023	4070
Lime & Shale	2753	2830	Lime	4070	4124
Lime	2830	2830			
Sandy Lime & Shale	2830	3000			



We hereby certify that the above is a true and correct record of the log on the well in the center of the Northwest quarter of the Northwest quarter of Section 8, Township 9 North, Range 13 West, Osborne County, Kansas.

OSBORN COUNTY

3 7 13W
75 24

Chester H. Westfall
COUNTY CLERK

ASST. SECY:

H. C. Cook
Asst Secy