


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

15-141-00018-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Osborne

County. Sec. 11 Twp. 9S Rge. 14W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW

Lease Owner Albert Markham, et al

Lease Name Heitschmidt Well No. 1

Office Address P. O. Box 500, McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-8-1950

Application for plugging filed " 19

Application for plugging approved " 19

Plugging commenced " 19

Plugging completed " 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Petty

Producing formation Depth to top Bottom Total Depth of Well 3922' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand	Water	70	85	8-5/8	173.83'	None
"	"	735	855			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Loaded hole with heavy mud to 170 feet. Set bottom plug at 170. Poured 1 sack hulls then mixed and poured 15 sacks cement through drill pipe. Heavy mud to 40 feet. Set top plug and poured one sack hulls, then mixed and poured 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to A. D. Allison & Co., Inc., Address 715 Brown Building, Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. A. ALLISON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Allison

715 Brown Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 13th day of December, 1950

My commission expires 7-22-53

Notary Public

PLUGGING  
FILE SEC 11 T 9 R 14  
BOOK PAGE 48 LINE 33

DEC 14 1950  
CONSERVATION DIVISION  
Wichita, Kansas

12-14-50

15-141-00018-00-00

ALBERT MARKHAM, et al  
#1 HEITSCHMIDT

Sec. 11, Twp. 9S., Rge. 14W.,

SW SW

Total Depth 3922'

Comm. 11-22-50

Comp. 12-8-50

Contr: A. D. ALLISON & CO., Inc.

Osborne County, Kansas.

PROD: D & A

Elev: 1914 Rotary Bushing

CASING RECORD:

8-5/8 173.83'

<u>FORMATION</u>	<u>DEPTH</u>
Surface and sand stone	70
Sand	85
Shale and shells	170
Lime and shale	285
Shale and shells	735
Sand	855
Shale and shells	1060
Shale and lime	1150
Red bed and anhydrite	1190
Shale and shells	1525
Shale and lime	1845
Lime and shale	2085
Lime	2145
Lime and shale	2415
Shale and lime	2485
Lime and shale	2640
Sandy shale	2680
Shale and lime	2820
Lime	3130
Lime and shale	3195
Lime	3565
Lime and shale	3740
Shale	3767
Chert and lime	3775
Lime	3815
Lime, cherty (Viola)	3850
Lime and shale	3922 T. D.

TOPS:

Topeka	2895
Heebener	3156
Brown Lime	3196
White Lime	3214
Cherty Conglomerate	3737
Viola	3788
Simpson Shale	3892

Certified true copy of drillers log.

By J. A. Allison

**PLUGGING**  
 FILE SEC 11 T 9 R 14 W  
 PAGE 48 LINE 33

RECORDED  
 STATE CORPORATION COMMISSION  
 DEC 14 1950  
 CONSERVATION DIVISION  
 Topeka, Kansas

12-14-50