

19-141-20119-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Osborne SEC. 29 TWP. 9 RGE. 14 E/W  
Location as in quarters or footage from lines:  
SW NW NE


Lease Owner Crude Producers, Inc.  
 Lease Name Delaney Well No. #1  
 Office Address Box 55 Russell, Kansas 67665  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed 11-1-81  
 Application for plugging filed 11-1-81  
 Plugging commenced 10-31-81 @ 11:45 pm  
 Plugging completed 11-1-81 @ 8:15 am  
 Reason for abandonment of well or producing formation Dry Hole

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3715'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS 8 5/8 set @ 224' Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 900' with heavy mud and mixed 70 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 210' with heavy mud and mixed 40 sacks of cement and pumped in hole thru drill pipe.

Filled hole to 40' built bridge pushed down plug and mixed 10 sacks of cement and filled hole to bottom of cellar; mixed 10 sacks and poured into the rat hole.

All cement used was Common 4% Gel 3% CC

RECEIVED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Revin Drlg., Inc. NOV 10 1981

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Russell, ss.  
Stanley C. Lingreen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Stanley C. Lingreen  
Box 293 Russell, Ks. 67665  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 81

Paula J. Gibson  
Notary Public.

My Commission expires: November 10, 1984