

15-141-20092-00-00
 STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80
 RECEIVED
 STATE CORPORATION COMMISSION
 OCT 25 1982 1029-82
 CONSERVATION DIVISION
 Wichita, Kansas
 RGE. 14W E/W

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Osborne SEC. 30 TWP. 9 RGE. 14W E/W
 Location as in quarters or footage from lines:
NE SE NE

Lease Owner Crude Producers, Inc.
 Lease Name Mravinec #1 Well No. _____
 Office Address P.O. Box 857 Russell, Kansas 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 10-12-82
 Plugging completed 10-14-82
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
 Producing formation _____ Depth to top _____ bottom T.D. 3341'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	234'	none
				4-1/2"		1809'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged off bottom with sand to 3250' and ran 5 sacks cement. Shot casing @2733',
 2516', 2326', 2011', 1811' and pulled a total of 45 joints of 4-1/2" casing.
 Plugged well with 5 sacks hulls, 15 sacks gel, 8-5/8" plug and 165 sacks 50/50 pos,
 4% gel, 6% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 82

My Commission expires:



Irene Hoover
 Notary Public.