

15-141-20090-00:00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Osborne County, Sec. 3 Twp. 9S Rge. 15W E/W

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

C. N/2 N/2

Lease Owner Graham-Michaelis Corporation

Lease Name BEISNER #1-3 Well No. #1-3

Office Address 211 N. Broadway, Box 247, Wichita, KS 67202

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed March 27 1981

Application for plugging filed March 27 1981

Application for plugging approved March 27 1981

Plugging commenced March 27 1981

Plugging completed March 27 1981

Reason for abandonment of well or producing formation

No commercial quantity of oil or gas encountered.

If a producing well is abandoned, date of last production


19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dwayne Rankin

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3865'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. @ 3865'

Set 1st Plug @ 720' with 70 sx.

Set 2nd Plug @ 240' with 30 sx.

Set 3rd Plug @ 40' Solid Bridge with 10 sx.

Rathole with 10 sx., 50-50 posmix, 4% gel, 3% c.c.

Plug was down @ 5:00 p.m., 3/27/81.

State Plugger - Dwayne Rankin.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice President (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Jack L. Partridge

801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 81

Suzanne M. Hoyer
Notary Public.

My commission expires 2/4/85



RECEIVED
STATE CORPORATION COMMISSION
4-1-81
APR - 1 1981
CONSERVATION DIVISION
Wichita, Kansas

CONTRACTOR'S WELL LOG 15-141-20090-00-00

OPERATOR: Graham-Michaelis Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: BEISNER #1-3
 LOCATION: C N/2 N/2, Section 3-9S-15W
 Osborne County, Kansas
 SPUD DATE: 3/18/81
 COMPLETION DATE: 3/27/81

0	70	Surface Clay & Sand Rock
70	256	Sand, Rock & Blue Shale
256	1198	Shale & Sand
1198	1230	Anhydrite
1230	1592	Sand & Shale
1592	2409	Shale
2409	2595	Shale & Lime
2595	2821	Shale
2821	3060	Shale & Lime
3060	3563	Lime
3563	3627	Conglomerate & Lime
3627	3690	Conglomerate & Viola
3690	3782	Viola
3782	3865	Viola, Simpson, & Arbuckle
	3865	Rotary Total Depth

Spud hole @ 1:30 p.m., 3/18/81. Cut 256' of a 12 1/4" hole. Lost circ. @ 70'. 4 3/4 hrs. mixed mud, got circulation back. Ran 6 jts. of 8 5/8" - 23# casing (tally 247.60') Set @ 254' RTD. Cemented with 180 sx. of common 3% c.c., 2% gel. Cement did circulate. Plug was down @ 11:30 p.m., 3/18/81. Will drill the plug @ 9:30 a.m., 3/19/81.

T.D. @ 3865'. Set 1st Plug @ 720' with 70 sx. Set 2nd Plug @ 240' with 30 sx. Set 3rd Plug @ 40' Solid bridge with 10 sx. Rathole with 10 sx., 50-50 posmix, 4% gel, 3% c.c. Plug was down @ 5:00 p.m., 3/27/81. State Plugger - Dwayne Rankin.

SAMPLE TOPS:
 Anhydrite 1198'
 B/Anhydrite 1230'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log the of BEISNER #1-3, C N/2 N/2, Section 3-9S-15W, Osborne County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 31st day of March, 1981.



Suzanne M. Hofer
 Suzanne M. Hofer, Notary Public

2/4/85