

15-141-2011-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Osborne SEC. 3 TWP. 9S RGE. 15W E/W  
Location as in quarters or footage from lines:  
SW SW NE


Lease Owner Midco Exploration, Inc.  
Lease Name BEISNER Well No. 1  
Office Address 2625 Butterfield Rd., Oakbrook, IL 60521  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 9/15/81  
Application for plugging filed 9/15/81  
Plugging commenced 9/15/81  
Plugging completed 9/15/81

Locate Well  
correctly on above  
Section Platt.

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 600' with 60 sx.  
Set 2nd plug @ 240' with 40 sx.  
Set 3rd plug @ 40' with 10 sx.  
5 sx. in Rathole. 50-50 posmix, 6% gel/

Plug was down @ 12:15 a.m., 9/15/81

RECEIVED  
STATE CORPORATION COMMISSION

SEP 24 1981

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Abercrombie Drilling, Inc. CONSERVATION DIVISION 924-81  
Wichita, Kansas


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of September 19 81

My Commission expires: 7-13-85



15-141-20111-0000

CONTRACTORS WELL LOG

OPERATOR:	Midco Exploration, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	BEISNER #1
LOCATION:	SW SW NE, Sec. 3-9S-15W Osborne County, Kansas
SPUD DATE:	9/08/81
COMPLETION DATE:	9/15/81

0	140	Topsoil, Sand & Shale
140	248	Shale
248	1189	Shale & Sand
1189	1224	Anhydrite
1224	2569	Shale
2569	3150	Shale & Lime
3150	3246	Lime & Shale
3246	3318	Lime
3318	3516	Lime & Chert
3516	3610	Lime
3610	3663	Lime & Chert
3663	3700	Lime
	3700	Rotary Total Depth

Spud hole @ 9:15 p.m., 9/08/81. Drilled 248' of a 12½" hole. Ran 6 jts. of new 8 5/8" 20# casing set @ 246' and cemented with 190 sx. common 3% c.c., 2% gel. Cement did circulate. Plug was down @ 2:00 a.m., 9/09/81.

3700' RTD. Set 1st plug @ 600' with 60 sx. Set 2nd plug @ 240' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 6% gel. Plug was down @ 12:15 a.m., 9/15/81.

SAMPLE TOPS:

Anhydrite	1189'
B/Anhydrite	1224'

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS        )  
                                  ) SS  
COUNTY OF SEDGWICK )

SEP 24 1981 9-24-81  
CONSERVATION DIVISION  
Wichita, Kansas


Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BEISNER #1, SW SW NE, Sec. 3-9S-15W, Osborne County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 21st day of September, 1981.

Elizabeth G. Terry  
Elizabeth G. Terry  
NOTARY PUBLIC



my commission expires 7-13-85