

15-141-20142-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Osborne County, Sec. 5 Twp. 9 Rge. 15 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
SE NW SE

Lease Owner Mai Oil Operations  
Lease Name Beisner Well No. 2  
Office Address Box 33, Russell, Kansas 67665  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry hole



Locate well correctly on above  
Section Plat

Date Well completed 7-18 1982  
Application for plugging filed 7-18 1982  
Application for plugging approved 7-18 1982  
Plugging commenced 7-18 1982  
Plugging completed 7-18 1982  
Reason for abandonment of well or producing formation  
Dry hole

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Thoman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3,650  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	273'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

- Fill hole w/heavy mud
- Push bridge plug to 930'
- Spotted 50 sax cement on plug thru 4 $\frac{1}{2}$ " drill pipe
- Push bridge plug to 279'
- Spotted 40 sax cement on plug thru 4 $\frac{1}{2}$ " drill pipe
- Push bridge plug to 40' w/ $\frac{1}{2}$  wax hulls on plug
- Dump 10 sax cement on plug to cellar
- Dump 5 sax cement in rat hole
- Dump 5 sax cement in mouse hole

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Shields Drilling Co., Inc.  
Shields Bldg., Russell, Kansas 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss. contractor  
R.L. SHIELDS (employee of owner) or (owner) or (operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) R.L. Shields  
Shields Bldg., Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of July, 1982

My commission expires May 12, 1986  
James M. Drilling  
Notary Public.



RECEIVED  
STATE CORPORATION COMMISSION  
8-4-82  
AUG 04 1982