

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-141-20,225

LEASE NAME Hartman

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

3,630 Ft. from S Section Line

3,630 Ft. from E Section Line

SEC. 5 TWP. 9 RGE. 15 (E) or (W)

COUNTY Osborne

Date Well Completed 2-25-86

Plugging Commenced 2-25-86

Plugging Completed 2-25-86

LEASE OPERATOR Shields Oil Producers, Inc.

ADDRESS Shields Bldg., Russell, Kansas 67665

PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	250'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Fill hole w/heavy mud. Push bridge plug to 1,325', spot 25 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 850', spot 100 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 300', spot 40 sax cement on plug thru 4 1/2" drill pipe. Push bridge plug to 40' w/ 2 1/2" sax hulls on plug, dump 10 sax cement on plug to cellar. Dump 10 sax cement in rat hole and 10 sax cement in mouse hole. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164

Address Shields Bldg., Russell, Kansas 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, Kansas 67665

SUBSCRIBED AND SWORN TO before me this 12th day of March, 1986

Ruth Phillips
 Notary Public

My Commission Expires:



RECEIVED
 STATE CORPORATION COMMISSION

MAR 13 1986

Form CP-4
 Revised 08-84

CONSERVATION DIVISION
 Wichita, Kansas

3-13-86