

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-197-20257-00-00

Spot: SENWSE

Sec/Twnshp/Rge: 23-12S-12E

1650 feet from S Section Line,

1693 feet from E Section Line

Lease Name: SS FARMS

Well #: 10-23

County: WABAUNSEE

Total Vertical Depth: 2408 feet

Operator License No.: 33116

Op Name: BERRY PETROLEUM COMPANY

Address: 1999 BROADWAY ST, STE 3700  
DENVER, CO 80202

String Size Depth (ft) Pulled (ft) Comments

PROD 5.5 2408 150 SX

SURF 8.625 364 218 SX

78-26

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 06/07/2007 8:00 AM

Plug Co. License No.: 33961

Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC

Proposal Rcvd. from: RICK STEVENS

Company: BERRY PETROLEUM COMPANY

Phone: (972) 381-2701

Proposed Plugging Method: BOTTOM PLUG: 2078-2212, MIDDLE PLUG: PERF & SQUEEZE 916-1414, TOP PLUG: 0-350.

Plugging Proposal Received By: TAYLOR HERMAN

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 06/07/2007 5:00 PM

KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran 2 7/8" tubing to 2212' and pumped 25 sacks of cement. Pulled tubing to 1427' and pumped 15 sacks of cement. Perforated the 5 1/2" casing at 350' and circulated 80 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
2200	2212		
2184	2189		
2173	2179		
2152	2159		
2128	2131		

RECEIVED  
KCC DISTRICT #3

MAY 29 2008

CHANUTE, KS

INVOICED

DATE 6-30-08

INV. NO. 2008061906

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 06 2008

Remarks:

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

PH