

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-197-20258-00-00
Spot: SESESE Sec/Twnshp/Rge: 23-12S-12E
422 feet from S Section Line, 479 feet from E Section Line
Lease Name: SS FARMS Well #: 16-23
County: WABAUNSEE Total Vertical Depth: 2338 feet

Operator License No.: 33116
Op Name: BERRY PETROLEUM COMPANY
Address: 1999 BROADWAY ST, STE 3700
DENVER, CO 80202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 2338 | | 150 SX |
| SURF | 8.625 | 359 | | 209 SX |

75.99

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/07/2007 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: RICK STEVENS Company: BERRY PETROLEUM COMPANY Phone: (972) 381-2701

Proposed Plugging Method: BOTTOM PLUG 2028-2165, MIDDLE PLUG : PERF. & SQUEEZE 866-1300, TOP PLUG: 0-350.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2007 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Ran 2 7/8" tubing to 2165' and pumped 25 sacks of cement. Pulled tubing up to 1379' and pumped 15 sacks of cement. Perforated 5 1/2" casing at 350' and circulated 80 sacks of cement to surface.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2153 | 2165 | | |
| 2142 | 2145 | | |
| 2123 | 2130 | | |
| 2105 | 2107 | | |
| 2078 | 2080 | | |

RECEIVED
KCC DISTRICT #3
MAY 29 2008
CHANUTE, KS

INVOICED
DATE 6-30-08
INV. NO. 2008061906

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 06 2008

Remarks:
Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

PHS