

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23442-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 29-9S-22W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: STURGEON Well #: 1-29
County: GRAHAM Total Vertical Depth: 4060 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 W 112TH
OKLAHOMA CITY, OK 73162

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 220 | | |

131.95

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/14/2008 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 06/14/2008 12:30 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 4016' w/25 sxs.
2nd. Plug at 1920' w/25 sxs.
3rd. Plug at 1130' w/100 sxs.
4th. Plug at 270' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 6-30-08
INV. NO. 2008061910

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 19 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce D Basye

(TECHNICIAN)

CM

Form CP-2/3

JUN 17 2008

PKS