

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01810-00-01
Spot: SWNWSW Sec/Twnshp/Rge: 5-8S-17W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: FORREST Well #: 3
County: ROOKS Total Vertical Depth: 1361 feet

Operator License No.: 31171
Op Name: CONTINENTAL OPERATING CO.
Address: 1221 MCKINNEY STE 3700
HOUSTON, TX 77010

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|--------------------|
| PROD | 5.5 | 700 | 350 | w/unknowns sxs cmt |
| SURF | 8.625 | 101 | 0 | w/100 sxs cmt |

44.23

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2008 3:00 PM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: RALPH BRUNGARDT Company: CONTINENTAL OPERATING CO. Phone: (713) 209-1110

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 4% gel - 300# hulls.
Original well TD was 3376'. Operator was only able to get down to 1361'.
Three drill collars left in the hole.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2008 6:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 880' - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls. - had circulation and ran out of cement.
Pulled tubing to 540' - pumped 45 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate cement.
Pulled all tubing and topped well off with 15 sxs 60/40 pozmix - 4% gel.

Perfs:

INVOICED
DATE 6-30-08
INV. NO. 2008061911

Remarks: ALLIED CEMENTING COMPANY-TICKET #32259.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 18 2008

CONSERVATION DIVISION
WICHITA KS

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

PAT

JUN 16 2008

V D SIDNEY #3 FORREST 5-8-17W
 SW NW SW
 Contr. _____ ROOKS _____ County
 E. 1904 Comm. _____ Comp. 7-13-56 IP 25 BOPD

| Tops | Depth | Datum | Casing |
|------|-------|-------|----------------|
| | | | 8" 100 |
| | | | 5" 3353 |
| LANS | 3070 | -1166 | ACID 1000 |
| ARB | 3352 | -1148 | LONE STAR POOL |
| ID | 3365 | -1161 | |

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

