

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00498-00-00
Spot: SESENW Sec/Twnshp/Rge: 5-16S-14W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: NUSS Well #: 1
County: BARTON Total Vertical Depth: 3425 feet

Operator License No.: 31341
Op Name: CRAIG, WARD DBA CRAIG OIL COMPA
Address: 15 S MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3425	0	w/unknown sxs cmt
SURF	8.625	306	0	w/unknown sxs cmt

11.31

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2008 12:30 PM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVID FUNK Company: CRAIG OIL COMPANY Phone: (785) 483-1543

Proposed Plugging Method: Ordered 285 sxs 60/40 pozmix - 4% gel - 450# hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2008 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

06/06/2008
Ran tubing to 3000' - pumped 50 sxs cement with 100# hulls and 16 sxs gel.
Pulled to 1500' - pumped 40 sxs cement 3% cc with 200# hulls. Well on vacuum.
Shut down one hour. Tagged cement at 2500' with sand line - shut down for the day.
06/07/2008
Ran tubing - tagged cement at 2000'.
Pulled on joint tubing - pumped 220 sxs cement with 600# hulls - circulated to surface.
Pulled tubing - topped off with 35 sxs cement.
S.I.P. 200#. Backside full.

Perfs:

INVOICED
DATE 6-30-08
INV. NO. 2008061912

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #1979.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 18 2008

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

JUN 10 2008

PPS

Contr. SHELLEY-MILLER BARTON County

E. 1933 RB Comm. 6-24-55 IP 161 BOPD
PHY POT

Tops	Depth	Datum	Casing
ANH	929	1004	8" 306 DST 3151-95/1 HR, 90'
			5" 3425 SL 0 & GCM, 120' H 0 &
HEEB	3084	-1151	GCM, 180' GSY OIL, BHP 1060#
			DST 3210-27/1/2 HR, 5' MUD, BHP 0#
LANS	3145	-1212	DST 3288-3330/1/2 HR, 20' MUD, BHP
			460#: DST 3332-74/1 HR, 80' WTRY
			MUD, BHP 880#: DST 3406-13/1/2 HR
CONG	3387	-1454	6' MUD, BHP 0#: PERF 36/3183-
			87: ACID 500: SWB 10 BOPH/8 HR
ARB	3404	-1471	NW
TD	3425	-1492	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS