

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-16310-00-00  
Spot: SESENE Sec/Twnshp/Rge: 5-16S-14W  
2970 feet from S Section Line, 330 feet from E Section Line  
Lease Name: NUSS Well #: 2  
County: BARTON Total Vertical Depth: 3417 feet

Operator License No.: 31341  
Op Name: CRAIG, WARD DBA CRAIG OIL COMPA  
Address: 15 S MAIN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3399	0	w/unknown sxs cmt
SURF	8.625	246	0	w/unknown sxs cmt

*111.05*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/09/2008 9:00 AM  
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES  
Proposal Rcvd. from: DAVID FUNK Company: CRAIG OIL COMPANY Phone: (785) 483-1543

Proposed Plugging Method: Ordered 260 sxs 60/40 pozmix - 4% gel - 600# hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/09/2008 12:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:  
Ran tubing to 3100' - pumped 75 sxs cement with 300# hulls and 12 sxs gel - had returns.  
Pulled to 1500' - pumped 160 sxs cement with 300# hulls - circulated to surface.  
Pulled tubing - topped off with 25 sxs cement.  
S.I.P. 300#.

Perfs:  
  
**INVOICED**  
DATE 6-30-08  
INV. NO. 2008061912

RECEIVED  
KANSAS CORPORATION COMMISSION  
  
**JUN 18 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING-TICKET #1980.  
Plugged through: TBG

District: 04 Signed Bruce Rodie  
(TECHNICIAN) *CM*

LEO J DREILING

#2 NUSS

5-16-14W  
SE SE NE

Contr. DREILING & SONS

BARTON

County

E 1939 RBComm.

Comp. 9-15-61

IP 40 BOPD/LANS

Tops	Depth	Datum
TOP	2840	-901
HEER	3077	-1138
TOR	3096	-1157
LANS	3145	-1206
ARB	3394	-1455
TD	3417	-1478

Casing  
 8" 246  
 5" 3399  
 DST 3158-93/1 HR, 1680' G, 60'  
 SL 0 & GCM, 90' HO & GCM, 90'  
 FROGGY 0, 210' 0, BHP 795#/20"  
 DD 3417: ACID 500: SWB 4 BOPH &  
 2 BWP/5 HRS: PB 3280: 24/3188-  
 94: ACID 2000: SWB 7 BOPH, 30%  
 WTR

NUSS POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS