

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-19135-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 15-20S-11W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BRENN A Well #: 5
County: BARTON Total Vertical Depth: 3320 feet

Operator License No.: 4871

Op Name: HITSCHMANN, CURTIS LEE DBA CURT's

Address: 742 N US HWY 281 *oil operations*
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3320	0	100 SX
SURF	8.625	234	0	130 SX

107.90

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/11/2008 8:00 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: CURTIS HITSCMANN

Company: CURT'S OIL OPERATIONS

Phone: (620) 793-2540

Proposed
Plugging
Method:

Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: BRUCE RODIE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/11/2008 4:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 2852' - pumped 50 sxs cement with 200# hulls.
Pulled tubing to 2582' - pumped 6 sxs gel.
Pulled tubing to 1382' - pumped 150 sxs cement with 450# hulls - circulated to surface.
Pulled tubing - tied to casing - pumped 100 sxs cement - circulated out of backside.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3309	3312		

INVOICED

DATE 6-30-08

INV. NO. 2008061914

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 24 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #35511.

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

Form CP-2/3

JUN 19 2008

PR

6-25 MAP NO. 15-20S-11W

STATE Kansas COUNTY Barton LOC NW NW SE

OPER Bea Drilling Co., Inc., Ellinwood, Kansas FT FR LINE

WELL #5 FARM Brenn "A" FT FR LINE

POOL Chase - Silica ELEV 1762 GR 1764 DI 1767 KB

CONT Co. Tools GEOL Ray Goodin

INT PTD 3340' Arb. test

FR 5-8-64 SPLD 5-11-64 COMP 6-2-64

TD 3320 FM Arb. PBTB 3317


PRODUCING FM FROM TO TREATMENT

Arb 3309-12 12 250A

Co P 50 BOPD + 80 BHPD (Gr. NA)

8-5/8" @234' w/130 Sx.

4 1/2" @3319 1/2' w/75 Sx



Data Inc.

KB Spl Tops			
Hb	2909 -1142	LKC	3058 -1291
Tor	2926 -1159	No BKC	cld
Dg	2940 -1173	Arb	3300 -1533
BL	3033 -1266	RTD	3320 -1553

#1(Arb)3302-20, Rec. 18', 3 1/2' dense dol w/scatt stn. 12 1/2' good xln dol, vug poros w/good sho + tr wtr. 1 1/2' grn sh. No DST RTD 3320', 4 1/2" @3319 1/2' w/75 Sx. GRN Log, CO 3317', PBTB, Pf. 12/