

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22937-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 22-11S-15W
990 feet from S Section Line, 4620 feet from E Section Line
Lease Name: EULERT RANCH C Well #: 1
County: RUSSELL Total Vertical Depth: 3450 feet

Operator License No.: 6194
Op Name: ESP DEVELOPMENT, INC.
Address: 1749 250TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3310	0	w/150 sxs cmt
SURF	8.625	211	0	w/135 sxs cmt

112.13

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/18/2008 8:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: _____ Company: ESP DEVELOPMENT, INC. Phone: (785) 625-6394

Proposed Plugging Method: Ordered 550 sxs 60/40 pozmix - 4% gel - 700# hulls.
DV Tool 900' - cement to surface.
Spot 5 sxs sand at 3263'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/18/2008 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1510' - pumped 12 sxs gel with 100# hulls - good circulation.
Changed over to cement - pumped 300 sxs cement with 600# hulls - good circulation.
Ran out of cement - still circulating gel - no cement returns.
Pulled 7 joints of tubing to 1300' - pump ordered more cement.
Pumped 55 sxs - good circulation of cement - pulled tubing out.
Topped off with 10 sxs - tube full.
Tied onto backside - pressured up - full.

Perfs:

INVOICED
DATE 6-30-08
INV. NO. 2008061924

Remarks: QUALITY OILWELL CEMENTING-TICKET #1990.

Plugged through: TBG


RECEIVED
KANSAS CORPORATION COMMISSION

JUN 23 2008

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed


(TECHNICIAN)

CM



STATE KANS COUNTY RUSSELL
 FIELD HAGAMAN N (LANSING/ARBUCKLE)
 OPER E S P DEV
 WELL C-1 EULERT RANCH
 API 15-167-22937-0000
 SPUD 11/09/1990
 DTD 3450 FTD ARBUCKLE

WELL CLASS DO
 STATUS OIL
 COMP 12/13/1990
 PSTD 3314

22-11S-15W
 N2 SW SW
 990FSL 4620FEEL SEC



LOC 4 MI SW PARADISE, KS CONTR: WESTERN KANSAS DRLG

Petroleum Information Corporation

IPP 36 BOPD GTY 20 NATURAL
 PROD ZONE: ARBUCKLE OPENHOLE 3311-3314

EL: 1845 KB 1844 DF 1840 GR

CSGS: 8 5/8 @ 211 W/ 135 SACKS
 5 1/2 @ 3310 W/ 150 SACKS
 TBGS: 2 3/8 @ 3311
 DRLG COMP 11/16/90 RIG REL 11/16/90
 DSTS: DST 1 2700-2720 TOPEKA
 REC 211 FT GAS 60 FT G4OCM 30 FT SOCM
 INIT OP 30M IFF 41 FFP 41
 FINAL OP 30M IFF 41 FFP 49

LOG TOPS:
 STONE CORRAL 917 +928
 TOPEKA 2678 -833
 HEEBNER 2930 -1085
 LANSING 2980 -1135
 BSE KANSAS CITY 3240 -1395
 ARBUCKLE 3308 -1463
 TD 3450 -1605

ISIP 165 30M FSIP 107 30M IHP 1540 FHP 1473
 DST 2 2985-3074 LANSING REC 680 FT G4MCW
 INIT OP 30M IFF 134 FFP 299 FINAL OP 45M IFF 331 FFP 386
 ISIP 568 30M FSIP 644 45M IHP 1658 FHP 1626
 DST 3 3293-3314 ARBUCKLE REC 60 FT GAS 65 FT OIL 200 FT MCO
 INIT OP 30M IFF 43 FFP 54 FINAL OP 45M IFF 76 FFP 97
 ISIP 794 30M FSIP 776 1H IHP 1904 FHP 1801

PERFS: ARBUCKLE OPENHOLE 3311-3314: DID NOT TREAT NO CORES
 GEOL: RANDY KILLIAN

KS 8-040291

Copyright 1991 Petroleum Information Corporation