

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-21957-00-01

Spot: SEWNNE

Sec/Twnshp/Rge: 18-24S-22E

4300 feet from S Section Line, 1900 feet from E Section Line

Lease Name: ERMEL B

Well #: 45

County: BOURBON

Total Vertical Depth: 692 feet

Operator License No.: 33247 •

Op Name: PETROL OIL & GAS, INC.

Address: PO BOX 34  
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	677	0	
SURF	6.625	20	0	

35

Well Type: EOR

UIC Docket No: E19329.36

Date/Time to Plug: 05/19/2008 11:30 AM

Plug Co. License No.: 31813

Plug Co. Name: BECKER, STEVE A. DBA A & A WELL SERVICE

Proposal Rcvd. from: DALE MALEY

Company: PETROL OIL & GAS, INC.

Phone: (913) 549-8442

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO 677' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 05/19/2008 1:30 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 674'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

Top	Bot	Thru	Comments
628	631		

RECEIVED  
KCC DISTRICT #3

MAY 21 2008 CPT

CHANUTE, KS

INVOICED

DATE 6-18-08

INV. NO. 2008061856

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 27 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: GPS NO.ERM 45 @ 2472' NSL & 1331' WEL.

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

## NOTICE OF INTENTION TO DRILL

Starting date 06 24 83  
Month Day Year

API Number

15-011-21,957

NE/4 Sec. Sec 18 T 24 S, R 22 East ~~XX~~Operator license # 5375980 ft. from N ~~XX~~ line of sectionOperator Hillenburg Oil Company1900 ft. from ~~XX~~ E line of sectionname & P.O. Box 94address Bronson, KS 66716Nearest lease or unit boundary line 980 feetCounty BourbonLease name Ermel B Well # 45Contact person Harold Hillenburg Sr.Surface pipe by alternate 1 or 2 XPhone (316) 939-4321Domestic well within 330 ft. X yes; Municipal well within one mile X yesContractor license # X no; X no

Contractor

Depth of fresh water none feetname & Company Tools

Lowest usable water formation

address

Depth to bottom of usable water 100 feetSurface pipe to be set X 20 feet

THIS PERMIT

Type equipment: rotary X air  cable Conductor pipe if any required  feetWell drilled for: oil X gas  SWD Ground surface elevation  feet MSLInj OWWOEst. total depth 750 feetWell class: infield X pool ext  wildcat X Into solid formation not less than 20 ft.

EXPIRES

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specs.

Date 06/17/83 Signature of operator or agent William R. ColeTitle Supt. Production\$40 Fee Paid 44546

To be filed with Kansas Corporation Commission

Date received 6-20-83

5 days prior to commencing well

Card to be typed

MHC / KOME 6/20/83

form C-1

State Corporation Commission of Kansas

Conservation Division

200 Colorado Derby Bldg.

202 W. 1st St.

Wichita, Kansas 67202

Wichita, Kansas  
CONSERVATION DIVISION

JUN 20 1963

(MAIL IN ENVELOPE)

RECEIVED  
STATE CORPORATION COMMISSION