

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21018-00-00
Spot: NENENE Sec/Twnshp/Rge: 16-33S-6E
4967 feet from S Section Line, 303 feet from E Section Line
Lease Name: FRY Well #: 7-A
County: COWLEY Total Vertical Depth: 3192 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3191		100 SX
SURF	8.625	160		75 SX

103.74

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/13/2008 8:00 AM
Plug Co. License No.: 33695 Plug Co. Name: MID-KAN WELL SERVICE, LLC
Proposal Rcvd. from: JERRY TOLE Company: PPSI Phone: (316) 265-3351

Proposed Plugging Method: SET CIBP, W/2 SXS CEMENT. PERFORATE @ 350', CIRCULATE 60/40 POZMIX 4% GEL TO SURFACE. PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2008 8:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

TESTED CASING @ 100#, HELD OK. PERFORATED 4-1/2" CASING @ 350'. RIH W/TUBING @ 3100', UNITED CEMENTING PUMPED 400# SAND ON BOTTOM. WAITED 30 MINUTES, UNITED CEMENTING MIXED & PUMPED 50 SACKS 60/40 POZMIX 4% GEL AND DISPLACED IN CASING. LAYED DOWN TUBING. SWEDGED INTO 4-1/2" CASING AND UNITED CEMENTING MIXED & PUMPED 115 SACKS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5-13-2008 @ 1615 P.M. UNITED CEMENTING TICKET #8475.

Perfs:

Top	Bot	Thru	Comments
3140	3146		

INVOICED

DATE 6-18-08
INV. NO. 2008061857

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 27 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: 5/14/2008, TAGGED TOP PLUG @ SURFACE.

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)