

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-19014-00-02
Spot: NWNWSW Sec/Twnshp/Rge: 34-29S-7W
2310 feet from S Section Line, 415 feet from W Section Line
Lease Name: WALTERS Well #: 2
County: KINGMAN Total Vertical Depth: 4216 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4148		
PROD	4.5	4216		135sx
SURF	8.625	204		150sx
T1	2.375	4083		

137.02

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/29/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RANDY NEWBERRY Company: _____ Phone: (620) 243-4293

Proposed Plugging Method: PER KCC REQUIRES.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 02/29/2008 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

HOLE AT 723' IN 2003, CIBP WAS SET @ 4050', PERFS SHOT @ 3754-3764, CEMENT TO SURFACE WITH 300 SXS. ON 2/13/2008 SET CIBP @ 3736' PUT 4 SXS OF CEMENT ON TOP, PRESSURED UP HELD 300 PSI, SET CIBP @ 1270', PER-ED @ 1255' CIRC. TO SURFACE 200 SXS, FELL BACK 120', ON 2/29/2008 TOPPED OF WITH 40 SXS, CUT OFF HEAD CEMENT ON BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
4152	4155		
4116	4130		

INVOICED
DATE 6-18-08
INV. NO. 0008061858

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 27 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED ALLIED CEMENTING FROM MEDICINE LODGE, TICKET #31407 60/40 4% POS

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)