

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07770-00-00
Spot: SESESE Sec/Twnshp/Rge: 11-15S-14W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: LANDON Well #: 4
County: RUSSELL Total Vertical Depth: 3388 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	10	2245	0	w/unknown sxs cmt
SURF	8.625	3328	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2008 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DISTRICT AGENT MARVIN Company: KANSAS CORPORATION COMMIS Phone: (316) 337-6200

Proposed Plugging Method: Brought 450 sxs 60/40 pozmix - 4% gel.
Re-ordered another 450 sxs cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2008 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran in with tubing. Stacked out at 580'. Got pump and power swivel.
Drilled out several bridges down to 750'.
Stopped making any progress. Bit/tubing binding and bouncing.
Hole taking fluid. Hauled in 160 bbls of drilling mud - weak circulation.
POOH. Ran back in open ended. Stacked out at 580'.
Pumped 450 sxs cement - cement circulated inside 8 5/8".
Pulled tubing out - tied onto 8 5/8" - pumped 60 sxs cement.
Circulated up 10 3/4" - 8 5/8" annulus - used no hulls.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 09 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34016. CN 20080005-001

Plugged through: TBG

District: 04

Signed _____

Marvin Mills
(TECHNICIAN)

CM

[Handwritten signature]

J. L. HALL

#1 LONDON

11-15-14W
SE SE SE

Contr.

RUSSELL

County

E 1RP6

Comm

6-22-39

Comp

9-10-39

IP

20²⁵ BOFD

Tops	Depth	Datum
ANHY	873	
LANS	3075	
MISS LM	3345	
ARE	3377	
TD	3388	

Casing

10" 2245
8" 3328

A/7000, SO 3185-90;
SO 3324-28, 3101
TD 3382, 350' OIH
Pmp 695/8 hr

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

11-15-14W
SE SE SE