

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-073-30269-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 8-22S-10E  
1230 feet from S Section Line, 1428 feet from E Section Line  
Lease Name: PIXLEE B Well #: A-1  
County: GREENWOOD Total Vertical Depth: 2340 feet

Operator License No.: 5697  
Op Name: JACKSON BROS., L.L.C.  
Address: 116 E 3RD ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2300		
SURF	8.625	125		

76.05

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/26/2007 8:00 AM

Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' cement plug @ 2245' 50' cement plug @ 802' 50' cement plug @ 150' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/04/2008 12:00 AM KCC Agent: MICHAEL HEFFERN

**Actual Plugging Report:**

set rock bridge @ 2245' mix & dump 6 sxs cement shot casing @ 802' & 482' could not pull casing, ran tubing to 800' pumped 50 sxs cement, pulled tubing to 350' pumped 55 sxs cement to surface. cement fell back to 177' pumped 25 sxs cement to surface.

RECEIVED  
KCC DISTRICT #3  
JUN 16 2008  
CHANUTE, KS

MH

**Perfs:**

INVOICED

DATE 6/24/08  
INV. NO. 2008061894

Remarks:  
Plugged through: TBG

District: 03

Signed Mike Heffern (TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 26 2008

CONSERVATION DIVISION  
WICHITA, KS

*PKT*