

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20255-00-01
Spot: SESWNW Sec/Twnshp/Rge: 12-10S-24W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: S E GANO UNIT Well #: 1-2
County: GRAHAM Total Vertical Depth: 4060 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4060	0	w/225 sxs cmt
SURF	8.625	191	0	w/150 sxs cmt <u>131.95</u>

Well Type: EOR UIC Docket No: E24173.3 Date/Time to Plug: 06/17/2008 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 700# hulls.
DV Tool 2117' circulate with 525 sxs.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/17/2008 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto the 8 5/8" - pressured up to 800# P.S.I. - full.
Tied onto the 4 1/2" - pumped 315 sxs 60/40 pozmix - 4% gel with 400# P.S.I. - shut down.
4 1/2" standing full.

Perfs:

Top	Bot	Thru	Comments
3801	3998		

INVOICED
DATE 7-2-08
INV. NO. 2009060020

Remarks: ALLIED CEMENTING COMPANY-TICKET #30245.

Plugged through: CSG

District: 04

Signed [Signature]

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUN 23 2008

CONSERVATION DIVISION
WICHITA, KS

JUN 18 2008

DON E. PRATT
HAYS, KS.

#2 GENE GANO

12-10-24W
SE SW NW

Contr. GARVEY DRLG.

Cty. GRAHAM

Geol. J. R. GREEN

Pool GANO SE

E. 2470 KB Cm. 9/12/69 Cp. 10/16/69 IP PMP 240 BOPD, NW/
LANS, 3972-78

API 15-065-20,255

LOG Tops	Depth	Datum
TOP	3543	-1073
HEEB	3760	-1290
TOR	3782	-1312
LANS	3800	-1330
BKC	4022	-1552
RTD	4065	-1595
LTD	4065	-1595

Csg. 8-5/8" 191/150 SX
 4 1/2" 4060/225 SX
 DV @ 2117/505 SX
 DST 3814-35/1', GTS/28", 795'
 GCO, 60' M & SGCO, 60' MSW,
 BHP 1176-1147#/30", FP 99-
 367#
 DST 3918-88/1', 1200' SM&HGCO,
 50' HOC SW, BHP 1236-1226#/
 30", FP 119-515#

CO & PF 3972-78; SWB DN, SWB
 LOTS GAS & 15 BO NAT, SD/12 HRS,
 FU 3100' CGO, SWB DN & SWB 12 1/2
 BO NAT, SWB TST 2 HRS, NO TST,
 A 250, POP
 NO CORES

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS