

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-023-20088-00-01  
Spot: NW Sec/Twnshp/Rge: 33-3S-41W  
1300 feet from N Section Line, 1500 feet from W Section Line  
Lease Name: LAMPE OWWO Well #: 1-33  
County: CHEYENNE Total Vertical Depth: 1500 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 100 GLENBOROUGH DR STE 100  
HOUSTON, TX 77067

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 1428       | 0           |          |
| SURF   | 8.625 | 209        | 0           |          |

48.75

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/30/2008 11:30 AM  
Plug Co. License No.: 34094 Plug Co. Name: J-BIRD WELL SERVICE INC.  
Proposal Rcvd. from: TOM THOMAS Company: NOBLE ENERGY, INC. Phone: (303) 228-4235

Proposed Plugging Method: Ordered 110 sxs 50/50 pozmix cement - no gel.  
Plug through tubing.  
Operator elected to use all cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/30/2008 3:00 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

8 5/8" surface casing set at 209' w/190 sxs cement.  
4 1/2" production casing set at 1540' w/125 sxs cement.  
TD 1500'. PBTD 1428'.  
Ran tubing to 1380' - pumped 35 sxs cement.  
Pulled tubing to 600' - pumped 35 sxs cement - cement to surface.  
Connected to 4 1/2" production casing - pumped 10 sxs cement.  
Max. P.S.I. 140#. S.I.P. 0#.  
Cement visible in surface pipe.

**Perfs:**

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 1396 | 1406 |      |          |

INVOICED

DATE 7-2-08  
INV. NO. 8009060021

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: BISON CEMENT COMPANY-TICKET #7732.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

**JUN 10 2008**  
CONSERVATION DIVISION  
WICHITA, KS

