


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sheridan County, Sec. 32 Twp. 8 Rge. 30 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C NE SE
Lease Owner Stawson Drilling Company, Inc.
Lease Name Cox A Well No. 1
Office Address 408 One Twenty Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-20 1968
Application for plugging filed 11-20 1968
Application for plugging approved 11-20 1968
Plugging commenced 11-20 1968
Plugging completed 11-20 1968
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	350'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st. plug was set @ 1675' with 100 sacks cement
2nd. plug was set @ 365' with 20 sacks cement
3rd. plug was set @ 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1968
CONSERVATION DIVISION
Wichita, Kansas

11-26-1968


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

Subscribed and sworn to before me this 22nd. day of November, 1968



My commission expires September 19, 1970 JOSEPH A. HESS Notary Public.

15-179-20162-00-00
L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

Company	Slawson Drilling Company, Inc. 408 One Twenty Bldg. Wichita, Kansas 67202	Sec. 32	Twp. 8	Rng. 30
Farm	Cox A No. 1	Location	C NE SE	
Total Depth	4316'	County	Sheridan	
Comm.	11-12-68 Comp. 11-20-68	Elevation:	2958'	K. B.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671		2955'	D. F.
			2953'	G. R.
		Casing Record	Cement Record	Production:
	350' - 8 5/8"		225 sacks cement	

Figures Indicate Bottom of Formations

0'	40'	Surface Clay
40'	80'	Surface Clay
80'	195'	Sand
195'	255'	Yellow Clay
255'	280'	Hard Sand
280'	351'	Blue Shale
351'	985'	Shale
985'	1140'	Sand & Shale
1140'	1330'	Shale
1330'	1405'	Gyp
1405'	1781'	Shale & Streaks of Sand
1781'	2010'	Shale
2010'	2260'	Shale, Gyp & Sand
2260'	2370'	Sand & Shale
2370'	2569'	Redbed & Shale
2569'	2605'	Anhy.
2605'	2800'	Shale & Shells
2800'	3014'	Shale
3014'	3130'	Lime
3130'	3725'	Lime & Shale
3725'	4316'	Lime
4316'	T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 26 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Cox A #1.

Leo F. Dreiling
 LEO F. DREILING

Subscribed and sworn to before me this 22nd. day of November 1968.



Joseph A. Hess
 JOSEPH A. HESS NOTARY PUBLIC

Commission expires: September 19, 1970