

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Thomas County. Sec. 36 Twp. 8 Rge. ~~30~~ 31 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SW4

Lease Owner The Texas Company

Lease Name M.A. Meeks Well No. 1

Office Address Bx. 2420, Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed June 29, 19 47

Application for plugging filed June 27, 19 47

Application for plugging approved June 28, 19 47


Plugging commenced June 28, 19 47

Plugging completed June 29, 19 47

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well C.D. Stough, Box 105, Hays, Kans.

Producing formation Arbuckle Depth to top Bottom Total Depth of Well 4942 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8"	430'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4942' to 430' Heavy Mud.
430' to 413' 15 Sax Cement
413' to 11' Heavy Mud.
11' to Top 10 Sax Cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Texas Company,
Address Box 1801, Wichita, Kans.



STATE OF Kansas, COUNTY OF Sedgwick, ss.
M.C. Harrell (employee of owner) or ~~owner or operator~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M.C. Harrell
M.C. Harrell
Box 1801, Wichita, Kans. (Address)

SUBSCRIBED AND SWORN to before me this 24th day of July, 19 47
Bertha W. Butts Notary Public.



PLUGGING
FILE SEC 36 T 8 R 3/18
BOOK PAGE 117 LINE 15

15-193-05050-00-00

LOG OF WELL

SHEET No. 2

District **Kansas**

Owner **The Texas Co.**

Farm **M. A. Meeks**

Well No. **1**

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
Surface Clay	25				ELEVATION.....2984 DF TOPS: Anhydrite.... 2600' Topeka..... 3800' Hebner..... 4005' Lansing..... 4040' Mississippi.. 4490' Arbuckle..... 4852' CASING RECORD: 13-3/8" OD 48# SS Casing set at 430' w/ 350 Sax Lone Star Cement
Shale & Sand	285 260				
Sand & Shale	400 115				
Shale	500 100				
Shale & Sand	550 50				
Shale	1500 950				
Shale & Sand	1810 310				
Shale & Lime	1930 120				
Shale & Shells	2175 245				
Shale & Lime	2235 60				
Shale & Shells	2300 65				
Anhy & Red Rock	2400 100				
Red Rock & Shale	2440 40				
Red Rock & Shells	2565 125				
Red Rock	2575 10				
Anhydrite	2635 60				
Lime	2700 65				
Shale	2715 15				
Shale & Lime	2800 85				
Red Bed & Lime	2950 150				
Lime & Shale	2985 35				
Red Rock & Lime	3138 153				
Lime & Shale	3176 38				
Red Rock & Lime	3362 186				
Lime & Shale	3432 70				
Lime	3583 151				
Lime & Shale	3627 44				
Red Sticky Shale	3662 35				
Lime	3708 46				
Lime & Shale	4210 502				
Broken Lime	4303 93				
Lime & Shale	4348 45				
Lime	4396 48				
Sandy Lime	4436 40				
Lime	4605 169				
Lime Cherty	4612 7				
Lime & Shale	4625 13				
Lime	3679 54				
Conglomerate	4705 26				
Lime & Shale	4718 13				
Lime & Cherty	4748 30				
Lime	4759 11				
Lime & Sand	4770 11				
Lime & Shale	4786 16				
Shale	4816 30				
Lime	4942 126				
Total Depth	4942'				

REMARKS:

Cored 4700-05, no show - 4729-33, no show - 4743-48, no show - 4843-55, no show - 4868-73, no show - 4937-42, no show - 6/3/47, Ran DST, Packer at 1834', TD 1930', Open 15 min, filled up 1000' fresh water.

PLUGGING
 FILE SEC. 36 T. 8 R. 31 N.
 BOOK PAGE 117 LINE 15