


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Thomas County. Sec. 4 Twp. 8S Rge. 32W (E) (W)
Location as "NE/CNW&SW&" or footage from lines SE SE SW
Lease Owner Aladdin Petroleum Corporation
Lease Name Koch Well No. 1
Office Address 809 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) XXXXXXXX, Dry Hole
Date well completed March 17, 19 61
Application for plugging filed March 17, 19 61
Application for plugging approved March 17, 19 61
Plugging commenced March 17, 19 61
Plugging completed March 17, 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5232 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	303'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- #1 Halliburton plug set @ 500' w/1/2 sack hulls cemented w/20 sacks cement through drill pipe.
- #2 Halliburton plug set @ 290' w/4 sack hulls cemented w/20 sacks cement through drill pipe
- #3 Halliburton Plug set @ 40' w/4 sacks hulls cemented w/10 sacks cement through cc. bbl.

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1962
CONSERVATION DIVISION
Wichita, Kansas

9-17-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E Drilling, Inc.,
Address 719 Union Center Bldg., Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne L. Brinegar (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne L. Brinegar
Wayne L. Brinegar, K & E Drilling, Inc.
719 Union Center Bldg., Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 14th day of September, 1962

My commission expires 6-65

Julene M. Bannon
Julene M. Bannon Notary Public.



Geol

15-193-19003-00-00

DRILLER'S WELL LOG

OPERATOR: ALADDIN PETROLEUM CORPORATION
809 Petroleum Building
Wichita, Kansas

WELL NAME: #1 KOCH
LOCATION: SE SE SW Sec. 4-8S-32W
Thomas County,
Kansas

CONTRACTOR: K & E DRILLING, INC.
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: March 4, 1961

CASING RECORD: 8 5/8" @ 303' w/225 sx

COMPLETED: March 17, 1961

ROTARY TOTAL DEPTH: 5232'

ELEVATION: 3055' KB

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Soil & clay	60
Sand	220
Sand and shale	280
Shale	1900
Sand	1980
Shale	2195
Shale and shells	2910
Shale	3095
Lime and shale	3250
Shale and lime	3415
Lime and shale	3590
Lime	3665
Lime and shale	3790
Lime	4295
Lime and shale	4357
Lime	4525
Lime and shale	4575
Lime	4660
Shale	4715
Lime	5232 RTD

RECEIVED
STATE CORPORATION COMMISSION
SEP 7 1962
CONSERVATION DIVISION
Wichita, Kansas
9-7-62

RECEIVED
STATE CORPORATION COMMISSION
SEP 7 1962
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Wayne L. Brinegar, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Subscribed and sworn to before me this 27th day of March, 1961.
Wayne L. Brinegar

My Commission expires: October 30, 1961.
Wildalee Wind - Notary Public.

Copy of Log + Plug Rpt
Set to Holly
3/29/61

K & E DRILLING, INC.



Rotary Drilling Contractors