

15-193-30018-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Thomas County, Sec. 13 Twp. 8S Rge. (E) 35 (W)
Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Placid Oil Company
Lease Name Heble Well No. 1
Office Address 600 Beck Building - Shreveport, Louisiana
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-29-64 19
Application for plugging filed 2-29-64 19
Application for plugging approved 2-29-64 19
Plugging commenced 2-29-64 19
Plugging completed 2-29-64 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols - Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4883 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug @ 600' with 200 sacks cement
Set second plug @ 320', mixed and displaced
20 sacks of cement through drill pipe.
Completed @ 8:30 A.M. 2-29-64

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1964

CONSERVATION DIVISION
Wichita, Kansas

3-18-64

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Murfin Drilling Company
Address 617 Union Center - Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (contractor) (employee of owner) or (owner/proprietor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Murfin
Murfin Drlg. Co., 617 Union Center, Wichita 2, Ks.
(Address)

Subscribed and sworn to before me this 16th day of March, 1964

My commission expires _____
ADELA MIZENER, Notary Public
My commission expires November 5, 1966

Adela Mizener
Notary Public.



WELL LOG

15193-30018-0000

COMPANY **Placid Oil Company**
FARM **Heble** NO. **One (1)**

SEC. 13 T. 8S R. 35W
LOC. **C/SE NE**

RIG. NO. **Two (2)**

TOTAL DEPTH **4883'**

COUNTRY **Thomas County**
KANSAS

COMM. **2-14-64**


COMP. **2-29-64**

SHOT OR TREATED

CONTRACTOR

Murfin Drilling Company

ISSUED



CASING

20 10
15 8 5/8" 286' w/250 sacks cement
12 6
13 5

ELEVATION **3263 KB**

PRODUCTION **D&A**

FIGURES INDICATE BOTTOM OF FORMATIONS

180 Surface
260 Sand
296 Blue Shale
1650 Shale
2265 Shale & Sand
2450 Shale, Sand & Gyp.
2825 Red bed & Gyp/
2856 Anhydrite
3045 Red bed & Shale
3190 Shale & Shells
3485 Shale
3575 Shale & Lime
3620 Lime & Shale
3710 Shale & Chalk
3800 Shale & Lime
4278 Lime & Shale
4325 Lime, Shale & Chert
4883 Lime & Shale
4883 RTD

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1964
3-18-64
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
County of Sedgwick } ss:

I, C. Robert Buford of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Heble #1 well.

C. Robert Buford
C. Robert Buford

Subscribed and sworn to before me this 9th day of March 1964

My Commission Expires: ADELA MIZENER, Notary Public
My commission expires November 5, 1966

Adela Mizener
NOTARY PUBLIC