

15-193-20201-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20,201
LEASE NAME Otto Schroeder #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER _____
SPOT LOCATION C SE NW NE

LEASE OPERATOR Abraxas Petroleum Corp.
ADDRESS Box 17485, San Antonio, Tx. 78217

SEC. 18 TWP. 8s RGE. 35w(E) or (W)
COUNTY Thomas

PHONE # (512) 828-5354 OPERATORS LICENSE NO. 6499

Date Well Completed _____
Plugging Commenced 8/26/85

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/26/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4757'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	289'	none
				4 1/2"	4756'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug job only - No pipe recovery. Pumped 10 gel & 10 cement down backside. Pumped 10 gel, 3 hulls, & 240 sacks 60/40 poz 8% gel 3% c.c. down 4 1/2".

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Csaing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524


RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1985

SUBSCRIBED AND SWORN TO before me this 11 day of September, 19 85

Irene Hoover
Notary Public

CONSERVATION DIVISION
Wichita, Kansas.
My Commission expires: _____



Schlumberger

**SIMULTANEOUS
DUAL LATEROLOG**

COUNTY
FIELD
LOCATION
WELL
COMPANY

COMPANY AGRAXAS PETROLEUM CORP
15-193-20201-00-00
WELL Otto SCHROEDER # 1
FIELD WILOCAT
COUNTY THOMAS STATE KANSAS

LOCATION
C SE NW NE
API SERIAL NO. SEC. TWP RANGE
18 8 35W

Other Services:
CNL/FOC - G
PML

Permanent Datum: GROUND LEVEL; Elev.: 3337'
Log Measured From K.B. 7 Ft. Above Perm. Datum
Drilling Measured From K.B.

Elev.: K.B. 3344
D.F. ---
G.I. 3337

Date	<u>05/19/80</u>	RECEIVED STATE CORPORATION COMMISSION	
Run No.	<u>ONE</u>	JUN 11 1980	
Depth-Driller	<u>4757'</u>	CONSERVATION DIVISION Wichita, Kansas	
Depth-Logger (Schl.)	<u>4756'</u>	@	@
Btm. Log Interval	<u>47</u>	@	@
Top Log Interval	<u>291'</u>	@	@
Casing-Driller	<u>8 5/8" @</u>	@	@
Casing-Logger	<u>291'</u>	@	@
Bit Size	<u>7 7/8"</u>	@	@
Type Fluid in Hole	<u>STARCH</u>	@	@
Dens.	<u>10.0</u>	ml	ml
Visc.	<u>40</u>	ml	ml
pH	<u>6.4</u>	ml	ml
Fluid Loss	<u>6.4</u>	ml	ml
Source of Sample	<u>CIRCULATED</u>		
Rm @ Meas. Temp.	<u>.187 @ 80 °F</u>	@ °F	@ °F
Rmf @ Meas. Temp.	<u>.199 @ 62 °F</u>	@ °F	@ °F
Rmc @ Meas. Temp.	<u>- @ - °F</u>	@ °F	@ °F
Source: Rmf Rmc	<u>m -</u>		
Rm @ BHT	<u>.131 @ 117 °F</u>	@ °F	@ °F
TIME			
Circulation Stopped	<u>0730 5/20</u>		
Logger on Bottom	<u>1100</u>		
Max. Rec. Temp.	<u>117 °F</u>	°F	°F
Equip. Location	<u>7780 COLBY</u>		
Recorded By	<u>MERRY POOLE</u>		
Witnessed By Mr.	<u>G. SEWELL</u>		