

15-193-30019-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Thomas County, Sec. 7 Twp. 8S Rge. 36W (E) (W)

Location as "NE/CNW/SW" or footage from lines C/NE NE

Lease Owner Morrison Producing Company

Lease Name FULWIDER Well No. One

Office Address 400 North Main - El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5/1/62 19

Application for plugging filed 5/1/62 19

Application for plugging approved 5/1/62 19


Plugging commenced 5/1/62 19

Plugging completed 5/1/62 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4971 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	314	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Displaced with mud to 300'. Set plug, mixed and displaced 25 sacks cement through Drill Pipe. Set top plug @ 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 31 1962

CONSERVATION DIVISION
Wichita, Kansas

5-31-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company

Address 617 Union Center Building - Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Fred Murfin

(Signature) Fred Murfin
617 Union Center Bldg. - Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of May, 1962

My commission expires June 14, 1964

Mary Louise Blume
Notary Public.



WELL LOG

15-193-30019-00-00


COMPANY Morrison Producing Company
FARM FULWIDER NO. One

SEC. 7 T. 8S R. 36W
LOC. C/NE NE

TOTAL DEPTH 4971'
COMM. 4/17/62 COMP. 5/1/62
SHOT OR TREATED No
CONTRACTOR Murfin Drilling Company
ISSUED

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1962
CONSERVATION DIVISION
Wichita, Kansas
5-31-62



CASING
20 10
15 8 5/8" 314' with 250 sacks cement
12 6
13 5

ELEVATION 3392' KB
PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 110' Surface Soil
- 235' Sand
- 1695' Shale
- 2290' Sand-Shale
- 2400' Shale & Lime Streaks
- 2410' Gyp
- 2690' Shale Gyp
- 2745' Gyp-Shale
- 2920' Red Bed-Sand-Shale
- 2954' Anhydrite
- 3000' Shale-Shells
- 3025' Shale & Gyp Streaks
- 3185' Shale
- 3340' Shale & Sand
- 3400' Shale-Lime
- 3862' Lime-Shale
- 3980' Lime
- 4080' Lime & Chalk
- 4700' Lime
- 4763' Lime & Shale
- 4879' Lime & Sand
- 4955' Lime
- 4965' Mississippi
- 4965' Rotary Total Depth

ELECTRIC LOG TOPS: Sample Tops not on Log:

- Webunsee 3734' Blaine 2605'
- Heebner 4144' Cimarron-
- Toronto 4174' Anhydrite 2920'
- Lansing/K. C. 4190'
- Base/K. C. 4500'
- Sand 4774'-4782'
- Sand 4846'-4856'
- Mississippi 4859'
- Log Total Depth 4971'

DST #3 4149'-4186' Open 45 min. Recovered 5' muddy water with few specks oil. IF 37# FF 37# IBHP 784#/20 min. FBHP 750/20 min.

DST #4 4190'-4232' Open 45 min. Recovered 30' watery mud. IF 37# FF 52# IBHP 1273#/20 min. FBHP 1159#/20 min.

DST #5 4240'-4256' Open 2 hrs. Recovered 300' salt water. IF 37# FF 149# IBHP 1311#/20 min. FBHP 1177#/20 min.

DST #6 4730'-4775' Open 1 hr. Recovered 100' muddy water. IF 60# FF 97# IBHP 1500#/20 min. FBHP 1311#/20 min.

DST #7 4920'-4965' Open 1 hr. Recovered 25' mud. IF 35# FF 50# IBHP 1197#/20 min. FBHP 970#/20 min.

DST #1 1768'-1788' Open 15 min. Recovered 75' mud & water. IF 15# FF 40# IBHP 2800/15 min. FBHP 270#/15 min.

DST #2 3818'-3862' Open 1 hr. Recovered 5' mud w/oil specks. IF 0# FF 0# IBHP 1122#/20 min. FBHP 224#/20 min. Weak blow 3 min.

State of Kansas
County of Sedgwick } ss:

I, Fred Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the FULWIDER #1 well.



Subscribed and sworn to before me this 29th day of May 19 62

My Commission Expires: June 14, 1964

Fred Murfin
May Rex Blum
NOTARY PUBLIC