

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-7-1982
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-141-20,136-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Graham-Michaelis Corporation

Complete Address Box 247, Wichita, Kansas 67201

Lease Name Krest Well No. #1-22

Location SW SW SE Sec. 22 Twp. 9 Rge. 15 (East) (West)

County Osborne Total Depth 3670'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company

Address 1720 Kansas State Bank Bldg., Wichita, Ks. 67202 License No. _____

Operation Completed: Hour: 9:15AM Day: 5th Month: June Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-259' s.p. cuc. w/160 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 270' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

Amount of Surface Casing: 259' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I would need a 4 wheel drive vehicle to get to location
due to muddy road conditions.

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 6-14-82

INVOICE NO. 478-W