

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20,102-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Ivan Holt Well Servicing, Inc.

Complete Address Box 401, Russell, Kansas 67665

Lease Name Harold Beck Well No. 1

Location SE SE SW Sec. 24 Twp. 9 Rge. 15 (~~East~~) (West)

County Osborne Total Depth 3653'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Red Tiger Drilling Co. and Allied Cementing Co., Inc.

Address 1220 Kansas State Bank Bldg, Wichita, KS License No. _____

Operation Completed: Hour: 4:30 PM Day: 11 Month: August Year: 1981

Plugging Operations attended by Agent? All Part _____ None _____

The above well was plugged as follows: 8 5/8" - 219' - 145 sacks circ. Anhydrite 1310' - 43' Elev. 2031 KB

Hole circulated and Filled with mud. 50 sacks cement pumped through drill pipe at 990'. 50 sacks cement pumped through drill pipe at 300'. Hole filled with mud to 40'. Plug and 1/2 sacks hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement.

Cement used: 50-50 Pozmix w/4% gel and 3% c.c.

RECEIVED
STATE CORPORATION COMMISSION
08-14-1981
AUG 14 1981

I hereby certify that the above well was plugged as herein stated

CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 9-28-81

INV. NO. 7602-11