

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20, 126-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Shields Oil Producers

Complete Address Box 709, Russell, Kansas 67665

Lease Name Kreft Well No. A-1

Location C 5/2 5/2 NW Sec. 26 Twp. 9 Rge. 15 (~~East~~) (West)

County Osborne Total Depth 3530'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Shields Drilling Co, Inc. and Allied Cementing Co, Inc.

Address Box 709, Russell, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 4:30 PM Day: 23 Month: November Year: 1981

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows: 8 3/8" - 259-165 sacks Common Ann. 1276-1314  
Elev. 2618 KB

Hole circulated and filled with mud. 50 sacks cement pumped  
through drill pipe at 900'. 50 sacks cement pumped through  
drill pipe at 300'. Hole filled with mud to 40'. Plug and 1/2  
sack hulls pushed to 40' and hole cemented to base of  
cellar with 10 sacks cement. Rathole cemented with 5 sacks  
cement. Mouse hole cemented with 5 sacks cement.  
Cement used: 50-50 Pozmix w/2% gel - 3% C.P.

RECEIVED  
STATE CORPORATION COMMISSION  
12-30-1981  
NOV 30 1981

I hereby certify that the above plugging instructions were given and stated.

**INVOICED**

Signed: [Signature]  
Conservation Division Agent

DATE 12-21-81  
INV. NO. 8792-U

CONSERVATION DIVISION  
Wichita, Kansas