

KANSAS

Form CP-3
Rev. 6-4-68



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-19166-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

11-29-71

Operator's Full Name Braden - Deem, Inc.

Complete Address 200 E. 1st Wichita, Kansas 67202

Lease Name Sarver Well No. 1

Location SW SW SW Sec. 1 Twp. 9 Rge. (E) (W) 16

County Rooks Total Depth 3460'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 10:30 A Day 26 Month 11 Year 1971

The above well was plugged as follows:

Total Depth 3460' 8 5/8 csg set at 239' cwc 175 sks.

4 1/2 csg set at 3459' cw 125 sk cmt.

4 1/2 csg perf. (3225-3232)

Filled 4 1/2 csg W/sd (3200-3460) Dumped 3 sk cmt W/dump bailer. (3165-3200)

Recovered 900' of 4 1/2 csg.

Pumped down 8 5/8 csg with 18 sk gel W/300 lbs hulls -70 sk 50-50 poz 6% -7 sk

gel -released plug and pumped 55 sk 50-50 poz 6% gel. By Allied cementing co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 12-1-71

INV. NO. 4720-W