

15-163-19178-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

MAY 10 1971
CONSERVATION DIVISION
Wichita, Kansas
5-10-1971

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name Baxter "A" Well No. 5

Location C E/2 SE NW Sec. 2 Twp. 9 Rge. (E) (W) 16

County Rooks Total Depth 3417'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling

Address Box 221 Great Bend, Kansas 67530 License No. 637

Operation Completed: Hour 11:30 A Day 3 Month 5 Year 1971

The above well was plugged as follows:

Total Depth 3417' 8 5/8 csg set at 203' cwc

4 1/2 csg set at 3416' cw 150 sk.

4 1/2 csg perf. 3165'

Set 4 1/2 wood plug at 3100' -poured 20' sd -dumped 4 sk cmt W/dump bailer. (3040-3100)

Recovered 700' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel W/3 sk hulls -70 sk poz 6% -7 sk gel -

release plug and pumped 50 sk poz 6%. Max pres. 500 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Messing
Well Plugging Supervisor

DATE 5/13/71

INV. NO. 3691-W